

LOCO RAIL TRACK FOUNDATION BOLT REPLACE AT COKE OVEN PLANT



Problem:

- Bolts of rail tracks breaking due to heavy load of raw material carrying loaded wagons.
- Acidic and hot water reactions with existing bolt
- Difficult to replace the bolts due to continuous work and running of rail

Solution:

- We used core cutting technique due to heavy reinforcements in the foundation.
- We are working here at the limited shut down time of 90 minutes without disturbing the daily work.