

## CEMENT GROUTING OF RCC WALL AT RAW WATER RESERVOIR



### Problem:

- Water leakages from the RCC wall construction joints and the honeycomb area.
- The Ground water table was high

### Solution:

- Provided treatment to the construction joint.
- We fixed the nozzle in a staggered position.
- Provided grout cement slurry with pressure grouting to stop the leakages.